

KANNUR UNIVERSITY
[Planning & Development Branch]

PLD/C1/5951/Creche/TVKRA/2022 (PART-I)

Date : ~~10~~/01/2023

NOTICE INVITING QUOTATIONS

Sealed competitive Quotations are invited from Registered/Authorised firms for the **Urgent Plumbing Works in the Creche** at the Thavakkara Campus, Kannur University, Kannur - 2.

The Quotations should reach the Registrar, Kannur University, Thavakkara Campus on or before **20/01/2023** at **3.00 pm** and will be opened at **3.30 pm** on the same day.

Conditions

1. The rate should be inclusive of all Taxes and nothing extra shall be admissible over and rate quoted.
2. Payment will be made through account payee Cheque and no advance payment will be sanctioned.
3. Work shall be completed in **15 days** from the date of Agreement.

The Engineering wing of the University shall be contacted during office hours to get details of the work. (Overseer-9048744011, Asst Engineer-9447888154)

The Registrar, Kannur University reserves the right to reject any of the Quotations or all the Quotations without assigning any reasons whatsoever.

sd/-
REGISTRAR(i/c)

To

1. Notice Board
2. Official Website
3. EE

QUOTATION SCHEDULE

Name Of Work: Urgent Plumbing Works in creche at Thavakkara Campus

SL. NO	QTY	PARTICULARS	UNIT	RATE INCLUDING ALL TAXES		AMOUNT (RS)
				IN FIGURES (RS)	IN WORDS (RS)	
1	2 nos	18.76.1 Cutting holes up to 30x30 cm in walls including making good the same:With common burnt clay F.P.S. (non modular) brick	nos			
2	13 m	50.18.9.18.1 Providing and fixing PVC pipes including fixing the pipe with clamps/clips at 1.00 m spacing. This included jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 75 mm dia 6Kgf/cm2 - External work- Exposed on wall	metre			
3	5 m	50.18.9.8.1 Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching,refilling & testing of joints complete as per direction of Engineer in Charge. 75 mm dia 6 Kgf/ cm2	metre			
4	8 nos	50.18.9.21.4 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 75 mm dia Bend	nos			
5	2 nos	50.18.9.21.5 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement -75x75x75 mm dia Tee	nos			
6	3 nos	50.18.9.21.9 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 75 mm dia Socket/coupling	nos			
7	18 m	50.18.7.3.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer- in-Charge 25 mm dia 12 Kgf/cm2 - Internal work - Exposed on wall	metre			
8	1 sqm	8.31 Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622(thickness to be specified by the manufacturer), of approved make, in all colours,shades except burgundy, bottle green, black of any size as approved by Engineerin-Charge,in skirting, risers of steps and dados, over 12 mm thick bed of cementmortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @3.3kg per sqm,including pointing in white cement mixed with pigment of matchingshade complete.	sqm			

9	1 nos	17.10.1.1 Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required:Kitchen sink with drain board510x1040 mm bowl depth 250 mm	nos			
10	1 nos	18.50.1 Providing and fixing C.P brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.15 mm nominal bore	nos			
11	1 nos	17.7.1 Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	nos			
12	1 nos	17.7.7 Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White Vitreous China Flat back wash basin size 450x300 mm with single 15 mm C.P.brass pillar tap	nos			
13	0.91 sqm	od268172/2022_2023 Providing and laying Polished Granite stone in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in Charge. Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	sqm			
TOTAL						
(Rupees.....Only)						
Signature:						
Name & Adress of the Quatationer:						
Date:						