Accredited By NAAC with 'B++' Grade Website: www.kannuruniversity.ac.in

PLD/E4/1247/Cabling & Wiring/TVKRA/2023

dated: 28.02.2024

Ref: Re-Tender Notice No. PLD/E4/1247/Cabling & Wiring/TVKRA/2023(I) dated 16.02.2024.

Re Tender for "LT Cable laying from 62.5 KVA DG Set to admin building Server Room at Thavakkara Campus"- Last date of receiving tenders- extended-reg

The last date for receiving of tender for "LT CABLE LAYING FROM 62.5 KVA DG SET TO ADMN BUILDING SERVER ROOM AT THAVAKKARA CAMPUS" is extended till 11/03/2024 at 2.30 PM. Time of opening - 3.00 PM

Registrar

KANNUR UNIVERSITY

TENDER SCHEDULE

NAME OF THE WORK: LT CABLE LAYING FROM 62.5 KVA DG SET TO ADMIN BUILDING SERVER ROOM AT THAVAKKARA CAMPUS

| | | | | LAST DATE O | F SUBMISSION: | -03-2024 , 2.30 pm |
|----------|----------|--|-------|-----------------|---------------|--|
| SL 10 | QUANTITY | ITEM DESCRIPTION | UNIT | RATE IN FIGURES | RATE IN WORDS | AMOUNT (Rs) |
| 1 | 210 | Supply and laying of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes in ground including excavation of trench of size 35x75 cm, refilling the trench etc.as required but excluding sand cushloning and protective covering(in ordinary soil). 3.5Cx95 sq mm. | meter | | | |
| 2 | 90 | Supply and laying and clamping of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1kV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60 cms, making good the damages, colour washing etc. as required 3.5Cx95 sq mm. | meter | | | |
| 3 | 2 | Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1KV grade as required 3.5Cx95 sq mm(45 mm). | nos | | | |
| 4 | 3 | Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of grade as required 3.5Cx240 sq mm(62 mm). | nos | | | |
| 5 | 1. | Supply and making straight through Joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1KV grade as required 3.5Cx95 sq mm. | nos | | | |
| 6 | 3 | Remove and reroute existing cable from Generator Panel to main Panel (3.5Cx240 sq mm Cable). | nos | | | |
| 7 | 1 | Preparation of drawing and documentation works including inspectorate approval. | unit | | | The same and the same at the s |
| | | Total Amount | | | | |
| | - | GST @ 18% | | | | |
| - | | Grand total | | | | |

| Only) |
|--------------|
| (RupeesOnly) |
| (Rupices |

SIGNATURE:

Name & Address of the of the Contractor:

Date: