

KANNUR UNIVERSITY
(Planning and Development Branch)
NOTICE INVITING QUOTATIONS

PLD/E4/20887/Water Supply/KUCL/TVKRA/2022
05.02.2024

Sealed competitive Quotations for the work of **Providing and fixing rain water Gutter in Library building at Thavakkara Campus** are invited from registered competent Contractors/firms. Name of the work shall be super scribed on the cover.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur -02 on or before 14 -2-2024 at 3.00pm and the Quotations will be opened at 3.30 pm on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted
2. The Contractor shall arrange all material & equipment and should be got approved by the Registrar through the Executive Engineer and work shall be executed as per KPWD specifications.
3. Payment will be made the through bank account and no advance payment will be sanctioned.
4. Work shall be completed within one month from the date of agreement.
5. The Defect Liability Period is 18 months from the date of completion of work.
6. Successful Quotationer shall deposit a sum equivalent to 3% of the value of the contract as Performance Guarantee within the period specified in the work order.
7. Quotation forms and details of works can be had from the www.kannuruniv.ac.in.
8. Quotation schedule is appended.

The Registrar, Kannur University reserves the right to reject any of the Quotations or all the Quotations without assigning any reason whatsoever.



Prof. (Dr.) Joby K Jose
Registrar

2

KANNUR UNIVERSITY

QUOTATION SCHEDULE

Name of work: Providing and fixing rain water Gutter in Library Building at Thavakkara Campus, Kannur

SL. NO	QTY	PARTICULARS	UNIT	RATE		AMOUNT (RS)
				IN FIGURES (RS)	IN WORDS (RS)	
1 CIVIL WORKS				<i>Last date of receipt: 14-02-2024, 3 PM</i>		
1	25	50.18.9.18.1 Providing and fixing PVC pipes including fixing the pipe with clamps/clips at 1.00m spacing . This included jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer in charge 75mm dia 6Kgf/cm ² - External work- Exposed on wall	metre			
2	10	50.18.9.21.2 Providing and fixing PVC moulded fittings/accessories for Rigid PVC pipes, including jointing with PVC solvent cement-75mm dia 45degree Elbow	nos			
3	35	od72592/2023- 2024 Providing and fixing 200mm PVC half split eave gutter, rain water connection arrangements, clamp, self drilling/self tapping screws, scaffolding charges complete including all cost and conveyance of all materials and labour charges.	metre			
TOTAL						
GST 18%						
GRAND TOTAL						
(Rupees.....Only)						

Signature:

Name & Address of the Quotationer:

Date: