

KANNUR UNIVERSITY  
(Planning and Development Branch)

NOTICE INVITING QUOTATIONS

PLD/E-4/13891/2025  
30.07.2025

Sealed competitive Quotations Super scribed as "Repairing water leakage in Syndicate room and Confidential Room at Thavakkara Campus" are invited from registered competent Contractors/firms.



Quotations with all details should reach the office of the Registrar, Kannur University, Kannur - 02 on or before 11/08 /-----2025 at 3 pm and the quotations will be opened at 11/08 ~~2025~~ 3.30 pm .

Conditions:

1. The amount quoted should be exclusive of GST and all other charges if any. GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted
2. The contractor shall arrange all material & equipment and should be got approved by the Registrar on recommendations of the Engineer in charge and work shall be executed as per KPWD specifications.
3. The Payment will be made the through bank account and no advance payment will be sanctioned
4. Work shall be completed within 3 months from the date of Agreement.
5. The Engineer in Charge shall be Assistant Engineer Civil
6. The defect Liability period shall be 6 months from the date of completion of the work. and the contractor shall be responsible to maintain all his works till completion.
7. Successful Quotationer shall deposit a sum equivalent to 5% of value of contract as Security Deposit within the period specified in the Work order.
8. The quotationer, before submitting the quotation for the work shall ensure that, the quotationer visited the Site and satisfied himself about the site conditions for the works (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen, and materials as well as permission from Authorities for this purpose
9. The Contractor shall make his own arrangements of Water and Electricity.
10. Quotation forms and details of works can be had from the [www.kannuruniv.ac.in](http://www.kannuruniv.ac.in).
11. Quotation Schedule is appended.

The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



  
Prof. (Dr.) Joby K Jose  
Registrar  




# KANNUR UNIVERSITY

## QUOTATION SCHEDULE

### REPAIRING WATER LEAKAGE IN SYNDICATE ROOM

SL. NO	QTY	PARTICULARS	UNIT	RATE	AMOUNT (RS)
		<b>CIVIL WORK OF SYNDICATE ROOM AT FIRST FLOOR</b>			
1	14.767	13.88 Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	m2		
2	21.487	13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	m2		
3	21.487	13.98.1 Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work	m2		
4	2.000	12.45.3 Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/ sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37 mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50 mm long with 6 mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25 mm	m2		
2		<b>CIVIL WORK OF CONFIDENTIAL ROOM AT SECOND FLOOR</b>			



1	14.803	13.88 Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	m2		
2	14.803	13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	m2		
3	14.803	13.98.1 Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work	m2		
4	10.021	13.6.1 20 mm cement plaster of mix: 1:4 (1 cement : 4 coarse sand)	m2		
3		<b>CIVIL WORK AT TERRACE FLOOR</b>			
1	0.097	15.7.4 Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	m3		
2	0.097	50.6.1.6 Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x20cm or nearest available size conforming to IS 2185 part I of 1979 for super structure above floor two level upto floor five level thickness 20cm and above in : CM 1:6 (1 cement : 6 coarse sand) etc complete	m3		
3	0.96	13.1.1 12 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)	m2		
4	0.96	13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	m2		
5	0.96	13.60.1 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work	m2		

