



**KANNUR UNIVERSITY**  
**(PLANNING AND DEVELOPMENT BRANCH)**  
**NOTICE INVITING RETENDERS**

PLD/E3/9409/2020 PartIV

27.01.2023

Sealed competitive Retenders superscribed as '2 KVA & 5 KVA UPS WIRING WORKS FOR SCHOOL OF WOOD SCIENCE AND TECHNOLOGY, 5 KVA UPS WIRING WORKS FOR CENTRE OF MANAGEMENT STUDIES AT MANGATTUPARAMABA CAMPUS' are invited from the registered competent Electrical Contractors/firms.

Sl.No.	Name of Work	EMD	Re Tender Fee	Time for the completion of Work	Last date of submission
1	2	3	4	5	6
1	2 KVA & 5 KVA UPS Wiring Works for School of Wood Science and Technology, 5 KVA UPS Wiring Works for Centre of Management Studies at Mangattuparamba Campus	Rs.3,670-	Rs.590/- including GST @ 18%	30 days from the date of Agreement	03/02/2023 at 3 PM

1. Tender Form can be had from Kannur University Website [www.kannuruniversity.ac.in](http://www.kannuruniversity.ac.in).
2. A sum of Rs.590/- (including GST @18% ) towards the cost of Tender form and an amount of Rs.3,670/- as EMD should be remitted separately by way of Demand Draft drawn in favour of Finance Officer, Kannur University, payable at SBI South Bazar Branch, Kannur or Kannur Branch of any other Nationalized or scheduled Bank.
3. The Tenderer should send along with the tender an initial agreement executed and signed in Kerala Stamp Paper of value ₹ 200/-.
4. The Tenderer shall have valid GST registration and shall furnish a copy of registration certificate along with the tender documents.
5. The successful Tenderer before signing the Agreement and within the period specified in the work order, shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit.
6. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.

7. Payment will be made through account and no advance payment will be sanctioned.
8. Received tenders will be opened on 03/02/2023 at 3 30 PM
9. Details of work can be had from the Planning and Development Branch on all working days up to 5pm.

The Registrar, Kannur University, reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.



REGISTRAR (i/c)



To

1. Notice Board
2. Website
3. EE

**KANNUR UNIVERSITY**  
TENDER SCHEDULE

**NAME OF THE WORK: 2 KVA & 5 KVA UPS WIRING WORKS FOR SCHOOL OF WOOD SCIENCE AND TECHNOLOGY, 5 KVA UPS WIRING WORKS FOR DEPARTMENT OF MANAGEMENT STUDIES AT MANGATTUPARAMABA CAMPUS**

LAST DATE OF SUBMISSION: 03/02/2023

SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE INCLUDING ALL TAXES		AMOUNT	REMARKS
				RATE IN FIGURES	RATE IN WORDS		
1	3	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCBIRCCB/Isolator6 way, Double door	each				
2	2	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc.as required. (But without MCBIRCCB/Isolator12way, Double door	each				
3	20	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.Single pole	each				
4	3	Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.40 amps	each				

5	1	Supplying and fixing following rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.25 amps	each				
6	2	Supplying and fixing following rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.40 amps	each				
7	320	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 2.5 sq. mm	mtr				
8	5	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 4 sq. mm	mtr				
9	55	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 6 sq. mm	mtr				
10	300	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.20 mm	mtr				
11	49	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.25 mm	mtr				
12	56	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.5/6 amps switch	each				

13	56	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.3 pin 5/6 amp socket outlet	each				
14	28	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.6 Module	each				
15	28	Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recessincluding making good the damages, colour washing, etc as required (RoHS compliant )6 module moulded plastic box on surface	each				
		<b>TOTAL AMOUNT</b>					

Rupees.....

**SIGNATURE**

**NAME OF THE CONTRACTOR**