


KANNUR UNIVERSITY
MANANTHAVADY CAMPUS
Edavaka Post, WAYANAD Dt. 670645 Ph: 9947111890

Sri.Hareendran P
Campus Director .

Mail cdmananthavady@kannuruniv.ac.in

KUC/Mndy/Works /Campus-2025/01

14-02-2025


Quotation Notice

Quotation for the Repair Works of Concrete Block Paving leading to Teacher Education Building and Dept of Rural & Tribal Sociology Building Kannur University Mananthavady Campus

Sealed competitive Quotations are invited from the authorized Workers /Contractors having proven track record for the “**Repair Works of Concrete Block Paving**” leading to Teacher Education Building and Dept of Rural & Tribal Sociology Building for Kannur University Mananthavady Campus Quotation with details of materials, price etc. should reach to the Campus Director, Kannur University, Mananthavady Campus, Edavaka P O, Mananthavady, Wayanad, -670645 Pin on or before 24/02/2025, 2 PM. The late quotations will not be accepted. The quotations will be opened at 3 PM on the same day in the presence of such of the quotationers or their authorized representatives who may be present at that time.

SCHEDULE

QUOTATION NOTICE NO	KUC/Mndy/Works /Campus-2025/01
NAME OF WORK	Repair Works of Concrete Block Paving
LOCATION TO SUPPLY & INSTALL	On the way to Teacher Education Building and Dept of Rural & Tribal Sociology Building for Kannur University Mananthavady Campus
QUOTATION SUBMISSION END DATE AND	TIME 24/02/2025 at 2pm
QUOTATION OPENING DATE AND TIME	24/02/2025 at 3pm




SPECIFICATION OF ITEMS OF USE AND WORK

Sl.No	Description of item	Quanty	Unit	Rate	Amount
1	Supplying and stacking at site.				
1.1	6mm size stone aggregate.	580.00	Cuft		
1.2	M sand.	150.00	Cuft		
1.3	Cement	12.00	bag		
2	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	150.00	Sqm		
3	Taking out existing CC interlocking paver blocks and laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer in- charge. (Old CC paver blocks shall be supplied by the department free of cost).	4237.00	Sqm		
	Total			Rs	

TERMS AND CONDITIONS

1. The total amount quoted should be inclusive of GST and all other charges, if any.
2. Quotation should be valid for a minimum period of three months.
3. Details of Warranty Condition and nearest service/maintenance centre should be provide along with quotation.
4. Supplier shall deliver and Fix the items at the locations mentioned above.
- 5-The payment in this regard will be made to the end beneficiary on production of bill and vouchers with satisfactory completion certification and on receipt of admissibility certificate from EE OF Kannur University within the approved estimate.
- 6-Supply of items and it,s Fixation work should be complete within 10 days of acceptance of supply or work order
7. The Campus Director ,Mananthavady Campus reserves the right to accept or reject the quotation and to trade or not to trade , without assigning any reason.



S/d

Campus Director ,Mananthavady Campus .

CAMPUS DIRECTOR
KANNUR UNIVERSITY
MANANTHAVADY CAMPUS
EDUKAKA, P.O, WAYANAD
KERALA, PIN - 670645