കണ്ണൂർ സർവ്വകലാശാല
KANNUR UNIVERSITY
Accredited By NAAC with 'B++' Grade
Website : www.kannuruniversity.ac.in

General Form of File PLD/E1/22502/2025 Approved by REGISTRAR (i/c) on 14-Nov-2026 01:13 PM - Page 1

PLANNING AND DEVELOPMENT BRANCH

NOTICE INVITING QUOTATIONS

PLD/E1/22502/2025

14.11.2026

Sealed competitive Quotations superscribed as "**Electrical work at KUTEC Kasaragod Campus**" are invited from registered competent Contractors/firms.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-2 on or before 27/11/2026 at 3.00 pm and the Quotations will be opened at 3.30 pm on the same day.

Conditions:

1. The rate quoted should be **inclusive of GST and all other charges if any.** The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange suitable materials and equipment and should be got approved by the Assistant Executive Engineer and work shall be executed as per KPWD specifications.
3. The Payment will be made through bank account and no advance payment will be sanctioned.
4. The successful bidder will be required to deposit Performance Guarantee/Security Deposit as per rules.
5. Work shall be completed within **45 days** from the date of agreement.
6. A Defect liability period of **2 years** will be applicable for this work, after completion.
7. Quotation forms and details of works can be had from the ***www.kannuruniv.ac.in***
8. The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.
9. Quotation schedule is appended herewith.

കണ്ണൂർ സർവ്വകലാശാല താവക്കര, കണ്ണൂർ-2

Sunil Kumar S
REGISTRAR (i/c)
കണ്ണൂർ സർവ്വകലാശാല
സിവിൽ സ്റ്റേഷൻ പി ഒ
താവക്കര, കണ്ണൂർ - 670002

To

1. Notice Board
2. Website

താവക്കര, സിവിൽ സ്റ്റേഷൻ പി.ഒ., കണ്ണൂർ 670 002 Thavakkara, Civil Station P.O., Kannur 670 002, Kerala, India
Phone :0497 -2715331 E-mail:registrar@kannuruniv.ac.in

KANNUR UNIVERSITY

QUOTATION SCHEDULE FOR ELECTRICAL WORK AT KUTEC KASARAGOD CAMPUS

LAST DATE OF SUBMISSION:

SL. NO	ITEM DESCRIPTION	UNIT	QUANTITY	RATE IN FIGURES	RATE IN WORDS	AMOUNT	REMARKS
1	Supply of commercial batten type integrated LED light fitting having color temperature not less than 5700K, system lumen output not less than 2000 and system wattage not more than 20 W, CRI not less than 80, extruded polycarbonate housing with PC diffuser, in-built electronic driver with surge protection not less than 2 kV etc. as required	Nos	20				
2	Supplying and fixing 5A to 32 A rating, 240/415 volts, 10 kA, ""C"" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double pole	Nos	12				
3	Supply, installation, testing and commissioning of 1200 mm sweep BEE-5 star rated ceiling fan with brushless direct current motor (BLDC) , class of insulation B , 3 no:s blades , 30 cm long down rod , 2no:s canopies, shackle kit, safety rope , copper winding, power factor not less than .9, service value (CM/M/W) minimum 6.00, Air delivery minimum 210 cum/min,350 RPM (tolerance as per IS :374-2019, THD less than 10% remote or electronic regulator unit for speed control and all remaining accesories including safety pin, nut and bolts , washers, temperature rise equal to 75 deg celsius (maximum) , insulation resistance more than 2 Megaohm , suitable for 230V,50 Hz, single phase AC supply , earthing etc., complete as required	Nos	18				
	TOTAL AMOUNT						
	GST 18%						
	GRAND TOTAL						

(Rupees .....Only)

SIGNATURE **REGISTRAR**

രജിസ്ട്രാർ (i/c)
കണ്ണൂർ സർവ്വകലാശാല
സിവിൽ സ്റ്റേഷൻ പി ഒ
താവക്കര, കണ്ണൂർ - 670007

Name & Address of the of the Quatationer

Date