

**KANNUR UNIVERSITY**  
(Planning and Development Branch)  
NOTICE INVITING QUOTATIONS

PLD/E-4/13890/2025

02.06.2026

Sealed competitive Quotations Super scribed as " **Fixing GI sheet around generator room and fixing gate in front of HT substation at Thavakkara Campus**" are invited from registered competent Contractors/firms.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur - 02 on or before ~~16-06-2026~~ at 3 pm and the quotations will be opened at 3.30 pm on the same day .

Conditions:

1. The rate quoted should be exclusive of GST and all other charges if any. GST charges and other charges, if any, should be furnished separately, and nothing extra shall be admissible over and above the rate quoted
2. The contractor shall arrange all materials & equipment and should be got approved by the Registrar on recommendations of the Engineer in charge and work shall be executed as per KPWD specifications.
3. The Payment will be made through the bank account, and no advance payment will be sanctioned
4. Work shall be completed within ~~---~~ 5 months from the date of the Agreement.
5. The Engineer in Charge shall be Assistant Engineer (Civil) Kannur University.
6. The defect Liability period shall be ~~---~~ 1 year from the date of completion of the work. and the contractor shall be responsible to maintain all his works till completion.
7. The successful Quotationer shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit within the period specified in the Work order
8. The quotationer, before submitting the quotation for the work, shall ensure that, the quotationer visited the Site and satisfied himself about the site conditions for the works (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen, and materials as well as permission from Authorities for this purpose
9. The Contractor shall make his own arrangements of Water and Electricity.
10. Quotation forms and details of works can be had from the [www.kannuruniv.ac.in](http://www.kannuruniv.ac.in).
11. Quotation Schedule is appended.

The Registrar, Kannur University, reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



Prof. (Dr.) Joby K Jose



## KANNUR UNIVERSITY

QUOTATION SCHEDULE

## FIXING GI SHEET AROUND GENERATOR ROOM AND FIXING GATE INFRONT OF HT SUBSTATION AT THAVAKKARA CAMPUS

SL. NO	QTY	PARTICULARS	UNIT	RATE		AMOUNT (RS)	REMARKS
				IN FIGURES (RS)	IN WORDS (RS)		
		<b>1 .Civil Works</b>					
1	42.000 sqm	OD Providing and fixing GI hard color powder coated traffod sheets 0.35 mm thick or nearest available thickness with overlaps of 150 mm at ends and GI hook or crank C.I. bolts and nuts including plain washers and bitumen washers etc complete	sqm				
2	395.202 kilogram	10.1 Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	kg				
3	46.500 kg	10.25.2 Item Shifted to head 14 as item 14.74 Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kg				



4	23.325 sqm	13.62.1 Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture .	sqm				
5	0.121 cum	4.1.5 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	cum				
6	2.000 no	OD Engaging labour for clearing site after dismanteling	no				
		<b>Total</b>					
		<b>18 % GST</b>					
		<b>Grand Total</b>					

(Rupees .....only)

Signature :

Name and Address of the quotationer :

Date :

