



**KANNUR UNIVERSITY**  
(PLANNING AND DEVELOPMENT BRANCH)  
NOTICE INVITING QUOTATION

PLD/E5/10206/2025

04.07.2025


Sealed competitive Quotations for "**Maintenance of wells near HT sub station at Thavakkara Campus**" are invited from registered competent Contractors/ firms. The name of work shall be superscribed on the cover.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-02 on or before ~~12.07~~ 2025 at 3 pm and the Quotations will be opened at 3.30p.m on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange suitable materials and equipment and should be got approved by the Registrar on recommendations of the Engineer in Charge and work shall be executed as per KPWD specifications. Asst. Executive Engineer(Civil), Kannur University shall be the Engineer-in-charge.
3. The Contractor shall ensure that before submitting quotation for the work, the Contractor visited the site and satisfied himself about the site conditions for constructions and for logistics and smooth flow of workmen and materials as well as permission from Authorities for this purpose.
4. The Payment will be made through bank account and no advance payment will be sanctioned.
5. Work shall be completed within 3 months from the date of agreement.
6. The Defect Liability Period shall be 1 year from the date of completion of work and the contractor shall be responsible to maintain all his works till completion of the Defect Liability Period and to hand over the work to the Engineer in charge .
7. Successful Quotationer shall deposit a sum equivalent to 5 % of the value of contract as performance Guarantee within the period specified in the work order.
8. Quotation forms and details of works can be had from the [www.kannuruniv.ac.in](http://www.kannuruniv.ac.in).
9. Quotation schedule is appended.

The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



Prof. (Dr.) Joby K Jose  
Registrar



# KANNUR UNIVERSITY

## QUOTATION SCHEDULE

*Last date of Receipt: 17.07.2025  
3 PM*

Name of work: MAINTENANCE OF WELLS NEAR HT SUBSTATION AT THAVAKKARA CAMPUS

SL. NO	QTY	PARTICULARS	UNIT	RATE		AMOUNT (RS)
				IN FIGURES (RS)	IN WORDS (RS)	
1 CIVIL WORKS						
1	100	2.32 Clearing grass and removal of the rubbish up to a distance of 50 m outside the periphery of the area cleared.	Sqm			
2	1.884	15.1 Demolishing lime concrete manually / by mechanical means and disposal of material within 50 metres lead as per direction of Engineer - in- Charges.	Cum			
3	0.629	2.25 Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	Cum			
4	1.884	7.1.1 Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with: Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum			
5	0.629	4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum			
6	0.450	13.1.2 12 mm cement plaster of mix: 1:6 (1 cement : 6 fine sand).	Sqm			



7	37.351	13.98.1 Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work	Sqm			
8	13.345	13.44.1 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm			
9	32.000	50.2.3.1 Pumping or Bailing out water and removing slush etc by using pump set including cost of labour, oil hire charges of pumpset, etc complete	hour			
10	7.443	2.6.1 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil	Cum			
11	21.289	2.26.1 Extra for every additional lift 1.5 m or part there of in excavation / banking excavated or stacked materials. All kinds of soil	Cum			
12	8.871	13.61.1 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	Sqm			
13	2.000	Providing well net above Grill for two wells	nos			
TOTAL						
GST 18%						
GRAND TOTAL						
(Rupees.....Only)						

Signature:

Name & Address of the Quotationer:

Date:

