KANNUR UNIVERSITY

Planning & Development Branch (C Section)

PI.D/C3/713/Legal Studies/2019

29.05.2023

NOTICE INVITING QUOTATIONS

Sealed Competitive Quotations are invited from Registered Contractors for the Sheet Roofing work for the Shuttle Badminton Court at School of Legal Studies at Thalassery Campus, Palayad of Kannur University.

Quotations with all relevant details should reach the Registrar, Kannur University, Thavakkara Civil station-PO, Kannur on or before **__07.06.2023**, **3.00PM** and will be opened at **3.30 pm** on the same day.

Conditions

- 1. The rate should be inclusive of all Taxes and nothing extra shall be admissible over and rate quoted.
- 2. The Payment will be made through account payee cheque and no advance payment will be sanctioned.
- 3. Work shall be completed in **20 days** from the date of agreement.

The Registrar, Kannur University reserves the right to reject any of the Quotations or all the Quotations without assigning any reasons whatsoever.

To

Sd/-

- 1. Notice Board
- 2. Website
- 3. Engineering Wing

Registrar (i/c)

QUOTATION SCHEDULE

NAME OF WORK: SHEET ROOFING FOR PAVILION OF SIZE: 6m x 2.4m FOR THE SHUTTLE COURT AT SCHOOL OF LEGAL STUDIES PALAYAD CAMPUS, KANNUR UNIVERSITY

| SL. NO | QUANTITY | PARTICULARS | UNIT | RATE | | AMOUNT |
|-----------|----------|--|------|--------------------|--------------|--------|
| | | | | IN FIGURES (RS) | IN WORDS | (RS) |
| 1 | 0.162 | 4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) | cum | | | |
| 2 | 14.4 | Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. | sqm | | | |
| 3 | 2.16 | 5.9.1 Centering and shuttering including strutting, etc. and removal of form for:Foundations, footings,bases of columns, etc for mass concrete | sqm | | | |
| 4 | 2.16 | 13.7.1 12 mm cement plaster finished with a floating coat of neat cement of mix:1:3 (1 cement : 3 fine sand) | sqm | | | |
| 5 | 311.131 | od399327/2022_2023 Steel work in built up G I tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position , including welding and bolted with special shaped washers etc. Complete | kg | | | |
| 6 | 66.875 | 10.1 Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete | kg | | | |
| 7 | 26.37 | 13.52.1 Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete.On steel work | sqm | | | |
| | | | | | Total | |
| | | | | | Add 18 % GST | |
| | | | | | Grand Total | |

Date: