



KANNUR UNIVERSITY
(Planning and Development Branch)
NOTICE INVITING RE-QUOTATIONS

PLD/E3/9228/2020

13.07.2023

Sealed competitive Quotations superscribed as "Street Light Repair works at Mangattuparamba Campus of Kannur University" are invited from registered competent Electrical Contractors/firms.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur -02 on or before 26-07-23 at 3.00 pm and the Quotations will be opened at 3.30 pm on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange all material & equipment and should be got approved by the Executive Engineer and work shall be executed as per KPWD specifications.
3. Payment will be made through bank account and no advance payment will be sanctioned.
4. Work shall be completed within 45 days from the date of Agreement.
5. Quotation forms and details of works can be had from the www.kannuruniv.ac.in.

The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



Dr. Joby K Jose
REGISTRAR (i/c)

a

KANNUR UNIVERSITY
QUOTATION SCHEDULE

NAME OF THE WORK: STREET LIGHT REPAIR WORKS AT MANGATTUPARAMBA CAMPUS

LAST DATE OF SUBMISSION: 26/02/2023

SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE INCLUDING ALL TAXES		AMOUNT	REMARKS
				RATE IN FIGURES	RATE IN WORDS		
		PART B					
1	100	Supply & laying of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes in ground including excavation of trench of size 35 x 75 cm, refilling the trench etc. as required but excluding sand cushioning and protective covering (in ordinary soil).2 core 10 sq mm	Mtr				
2	4	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.2 X 10 sq. mm (19mm)	Nos				
3	1	Insulation Testing works for existing street light cable,Light Fixing service charge	Ls				
4	1	Asphalt Cutting and repairing works	Ls				
		TOTAL AMOUNT					

*Rate including GST
(RupeesOnly)

SIGNATURE

Name & Address of the Quotationer

Date