Accredited By NAAC with 'B++' Grade Website: www.kannuruniversity.ac.in

PLD-E/E5/7966/2021

Date:26/07/2024

Reference: 1. Re-Quotation Notice No. PLD-E/E5/7966/2021 dated :29.06.2024,

2. Extension notice No. PLD-E/E5/7966/2021 dated 12.07.2024

Re-quotation for "Maintenance works at Ladies Hostel, Nileswaram Campus of Kannur University" -Last date of receiving of Quotation -extended -reg.

The Last date for receiving of re-quotation "Maintenance works at Ladies Hostel, Nileswaram Campus of Kannur University" is extended till 09.08.2024 at 3 PM. Time of opening -3.30 PM

A SITY & SITY &

REGISTRAR

## KANNUR UNIVERSITY

QUOTATION SCHEDULE

- Last date of secret: 09.08.2024

3 pm

Name Of Work: MAINTENANCE WORK OF LADIES HOSTEL AT NILESWARAM CAMPUS RATE INCLUDING ALL TAXES AMOUNT **PARTICULARS** UNIT QTY (RS) NO IN FIGURES IN WORDS (RS) (RS) 15.23.1 Dismantling tile work in floors and roofs laid in cement Sqm 1 mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm 11.41.2 Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to 2 Sqm 30 IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4(1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 600 x 600 mm. 17.69.2 Providing and fixing PTMT Waste Coupling for wash basin 3 and sink, of approved quality and nos colour.Waste coupling 38 mm dia of 83 mm length and 77 mm breadth, weighing not less than 60 gms 50.18.9.7.1 Providing and fixing PVC pipes includings of pipes with one 4 step PVC solvent cement, trenching refilling metre & testing of joints complete as per direction of Engineer in Charge. 63 mm dia 6Kgf/cm2 50.18.9.17.1 Providing and fixing PVC pipes including fixing the pipe with clamps/ clip at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent metre 5 cement and testing of joints complete as per direction of Engineer-in-Charge 63 mm dia 6 Kgf/cm2 -External work - Exposed on wall 50.18.9.20.1 Providing and fixing PVC moulded fittings/ accessories for 6 nos Rigid PVC pipes, including jointing with PVC solvent cement - 63 mm dia Elbow 50.18.9.20.9 Providing and fixing PVC moulded fitting / accessories for nos 7 Rigid PVC pipes, including jointing with PVC solvent cement-63 mm dia Socket /coupling 50.18.9.14.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and metre 8 testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 10 Kgf/cm2 - External work- Exposed on wall 9 Disposal work of wastes in waste bin unit TOTAL Signature: Name & Adress of the Quotationer:

Date: