

PLD/E1/24185/2025

02/09/2026

Ref: Tender No. PLD/E1/24185/2025 (I) dated, 18/08/2026.
Sub: UPS Wiring work for Physics Department at Payyannur Campus of Kannur University -tender date extended.

The last date for receiving tenders for the **UPS Wiring work for Physics Department at Payyannur Campus of Kannur University** is extended till 14.09.2026, 3.00 p.m and time of opening is 3.30 p.m. on the same day.

REGISTRAR(i/c)

Assistant Registrar -
PLD Branch
Kannur University



KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING TENDERS

PLD/E1/24185/2025 (I)

18.08.2026

Sealed competitive Tenders, superscribed as "UPS Wiring work for Physics Department at Payyannur Campus of Kannur University" are invited from registered competent electrical Contractors/firms.

Name of Work	Estimate amount	EMD	TENDER FEE	Time for the completion of work	Last date and time of submission
UPS Wiring work for Physics Department at Payyannur Campus of Kannur University	Rs. 2,58,730/-(inclusive of GST).	₹6,470/-	₹590/- (GST18% included)	3 months from the date of agreement	<u>02/09/2026</u> --- at 3 PM

- 1.Tender Form can be downloaded from the Kannur University Website www.kannuruniversity.ac.in.
- 2.A sum of ₹590/- (GST 18% included) towards the cost of Tender form and an amount of ₹6,470/- as EMD should be remitted **separately** by way of Demand Draft drawn in favour of Finance Officer, Kannur University, payable at SBI South Bazar Branch, Kannur or Kannur Branch of any other Nationalized or scheduled Bank.
- 3.The Tenderer should send along with the tender an initial agreement executed and signed in Kerala Stamp Paper of value ₹.200/-.
- 4.The Tenderer shall have valid GST registration and shall furnish a copy of registration certificate along with the tender documents.
- 5.The successful Tenderer before signing the Agreement and within the period specified in the work order, shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit.
6. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
7. Payment will be made through account and no advance payment will be sanctioned
8. Received tenders will be opened on 2-9-2026 at 3.30 PM.
- 9.Details of work can be had from the Engineering wing of the University, Thavakkara, Kannur, on all working days up to 5 pm.
10. The Registrar, Kannur University, reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.



To : 1.Notice Board.
2.Website

KANNUR UNIVERSITY							
TENDER SCHEDULE FOR UPS WIRING WORK PHYSICS LAB PAYYANUR CAMPUS							
LAST DATE OF SUBMISSION:							
SL. NO	ITEM DESCRIPTION	UNIT	QUANTITY	RATE IN FIGURES	RATE IN WORDS	AMOUNT	REMARKS
1	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 8 way (4+24), Double door TPN DB	EACH	1				
2	Supplying and fixing 5A to 32 A rating, 240/415 volts, 10 kA, ""C"" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole MCB	EACH	20				
3	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 amps 4 pole isolator	EACH	1				
4	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required. 3 Module 3 MD Plate	EACH	23				
5	Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant) 3 module moulded plastic box on surface 3 md box	EACH	23				
6	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required. 6 Module 6 md box	EACH	13				
7	Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant) 6 module moulded plastic box on surface 6 md plate	EACH	40				
8	Supplying and fixing following piano type switch / socket on the existing switch box/ cover including connections etc. as required. 5/6 amps switch 6 a switch	EACH	40				

9	Supplying and fixing following piano type switch / socket on the existing switch box/ cover including connections etc. as required.3 pin 5/6 amp socket outlet 6 amp socket	EACH	40				
10	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.20 mm 20 mm pvc pipe	METRE	300				
11	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.25 mm 25 mm pvc pipe	METRE	150				
12	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 2.5 sq. mm 2.5 sq mm wire	METRE	800				
13	Supplying and fixing following piano type switch / socket on the existing switch box/ cover including connections etc. as required.15/16 amp switch 16 A SWITCH	EACH	8				
14	Supplying and fixing following piano type switch / socket on the existing switch box/ cover including connections etc. as required.6 pin 15/16 amp socket outlet 16 Amp socket	EACH	8				
	TOTAL AMOUNT						
	GST 18%						
	GRAND TOTAL						
(RupeesOnly)							
SIGNATURE				REGISTRAR			
Name & Address							
Date							