

KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)

NOTICE INVITING TENDERS

PLD/D-2/10730/2025

29.09.2025

Sealed competitive Tenders, superscribed as Reconstructing the damaged portion of compound wall near School of Legal Studies, Palayad Campus' are invited from registered competent Contractors/firms.

The Details are as follows.

Sl.No.	Name of Work	EMD	Tender fee	Time for the completion of work	Last date and time of submission
1	2	3	4	5	6
1	Reconstructing the damaged portion of compound wall near School of Legal Studies, Palayad Campus	Rs.5,225/-	₹500/- (GST18% included)	3 (Three) months from the date of execution of agreement	21 /10/2025 at 3 PM

1. Tender Form can be downloaded from the Kannur University Website www.kannuruniversity.ac.in.
2. A sum of ₹500/- (GST 18% included) towards the cost of Tender form and an amount of Rs.5,225/- as EMD should be remitted separately by way of Demand Draft drawn in favour of Finance Officer, Kannur University, payable at SBI South Bazar Branch, Kannur or Kannur Branch of any other Nationalized or scheduled Bank.
3. The Tenderer should send along with the tender an initial agreement executed and signed in Kerala Stamp Paper of value ₹ 200/-.
4. The Contractor shall ensure that before submitting tender for the work, the Contractor visits the site and satisfies himself about the site conditions for construction and for logistics and smooth flow of workmen and materials as well as permission from the Authorities for this purpose.
5. The Tenderer shall have a valid GST registration and shall furnish a copy of the registration certificate along with the tender documents.
6. Assistant Engineer(Civil), Kannur University shall be the Engineer-in-Charge.
7. The Defect Liability Period shall be 1 year from the date of completion of work, and the contractor shall be responsible to maintain all his works till completion of the Defect Liability Period and to hand over the work to the Engineer in charge.
8. The successful Tenderer before signing the Agreement and within the period specified in the work



order, shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit.

9. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges, and other charges, if any, should be furnished separately, and nothing extra shall be admissible over and above the rate quoted.

10. Payment will be made through the account, and no advance payment will be sanctioned

11. Received tenders will be opened on 21/10/2025 at 3.30 PM.

12. Tender schedule is appended.

The Details of work can be had from the Engineering wing of the University, Thavakkara, Kannur, on all working days up to 5 pm.

The Registrar, Kannur University, reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.


Registrar

REGISTRAR (I/C)
KANNUR UNIVERSITY
CIVIL STATION P. O.
KANNUR-670 002

To : 1. Notice Board
2. Website



KANNUR UNIVERSITY						
TENDER SCHEDDULE						
NAME OF WORK :- CONSTRUCTION OF COMPOUND WALL AT SCHOOL OF LEGAL STUDIES,PALAYAD.						
SL. NO	QUANTITY	PARTICULARS	UNIT	RATE		AMOUNT
				IN FIGURES (RS)	IN WORDS (RS)	
1	12.600	2.8.1 Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil	cum			
2	1.401	4.1.6 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size)	cum			
3	1.800	5.1.2 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size	cum			
4	6.000	5.9.5 Centering and shuttering including strutting, etc. and removal of form for:Lintels, beams, plinth beams , girders bressumers and cantilevers	sqm			



5	198.000	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more.	kilogram			
6	8.881	50.6.7.2 Laterate masonry with neatly dressed laterate stone of size 40x20x15cm or nearest size in cement mortar 1:6 for super structure above plinth level up to floor two level including all cost of materials, labour charges etc	cum			
7	6.721	od Laterate masonry with departmental laterate stone of size 40x20x15cm or nearest size in cement mortar 1:6 for super structure above plinth level up to floor two level including all cost of materials, labour charges etc.(Modified 50.6.7.2)	cum			
8	64.000	13.1.1 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	sqm			
9	64.000	13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	sqm			
10	64.000	13.44.1 Finishing walls with water proofing cement paint of required shade:New work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm			
		Total				
		GST 18%				
		Grand Total				
(Rupees.....Only)						

Signature:

Name & Adress of the Tenderer:

Date:

