



KANNUR UNIVERSITY
(Planning and Development Branch)
NOTICE INVITING QUOTATIONS

PLD/E3/3806/2015 VOL. II

26.08.2025

Sealed competitive Quotations superscribed as **"Solid Block Masonry Work on Machine Room of Lift at Library Building, Thavakkara Campus"** are invited from registered competent Contractors/firms.

Completed Quotations should reach the office of the Registrar, Kannur University, Kannur - 02 on or before **09/09/2025** at **3:00** pm and the Quotations will be opened at **3:30** pm on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange all material & equipment and should be got approved by the Engineer in Charge and work shall be executed as per KPWD specifications.
3. Payment will be made through bank account and no advance payment will be sanctioned.
4. The Quotationer shall have valid GST registration and shall furnish a copy of registration certificate along with the tender documents.
5. The successful Quotationer before signing the Agreement and within the period specified in the work order, shall deposit a sum equivalent to 5% of the value of the contract as Performance Guarantee.
6. The Quotationer, before submitting Quotation for the work shall ensure that, the Quotationer visited the Site and satisfied himself about the site conditions (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen, and materials as well as permission from Authorities for this purpose.
7. Work shall be completed within 5 months from the date of Agreement.
8. The Engineer in Charge shall be Assistant Engineer(Civil)
9. Quotation forms and details of works can be had from the www.kannuruniv.ac.in.
10. Defect Liability period shall be 1 year from the date of Agreement.

The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.

Prof. (Dr.) Wilson V A
Development Officer (Registrar in-Charge)

KANNUR UNIVERSITY**QUOTATION SCHEDULE****SOLID BLOCK MASONRY WORK ON MACHINE ROOM OF LIFT AT LIBRARY BUILDING,THAVAKKARA CAMPUS**

SL. NO	QTY	PARTICULARS	UNIT	RATE		AMOUNT (RS)	REMARKS
				IN FIGURES (RS)	IN WORDS (RS)		
		1 .Civil Works					
1	2.700 sqm	15.57 Dismantling aluminium / Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 metres lead as directed by Engineer - in-Charge	sqm				

2	21.600 sqm	<p>14.72</p> <p>Providing and fixing double scaffolding system (cup lock type) on the exterior side, upto seven story high made with 40 mm dia. M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staricase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required location with essential safety features for the workmen etc. complete as per directions and approval of Engineer- in Charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding. Note:- This item to be used for maintenance work judicially, necessary deduction for scaffolding in the existing item to be done .</p>	sqm				
3	2.690 cum	<p>50.6.2.3</p> <p>Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure above floor two level upto floor five level with thickness 15cm in : CM 1:6 (1 cement : 6 coarse sand) etc complete</p>	cum				
4	13.448 sqm	<p>13.1.1</p> <p>12 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)</p>	sqm				

5	13.448 sqm	13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	sqm				
6	13.448 sqm	13.60.1 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work	sqm				
		Total					
		18 % GST					
		Grand Total					

(Rupeesonly)

Signature :

Name and Address of the quotationer :

Registrar

Date :