General Form of File PLD/E3/26884/2025 Approved by REGISTRAR (i/c) on 30-Oct-2026 09:17 PM - Page 1

KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING RETENDERS

PLD/E3/26884/2025 **30.**10.2026

Sealed competitive retenders superscribed as" **Replacement of the damaged GI Pipeline system in the Main block of Mangattuparamba Campus**" are invited from registered competent Contractors/firms.

Sl.No	Name of Work	EMD	Tender Fee	Time for the completion of work	Last date of submission
1	2	3	4	5	6
1	**Replacement of the damaged GI pipeline system in the Main block of Mangattuparamba Campus**	Rs.9,025/-	Rs.852/- including GST @ 18%	3 months	12.11.2026 & 3.00 PM

1. Tender Form can be had from Kannur University Website www.kannuruniversity.ac.in.
2. A sum of Rs.852 (including GST @18%) towards the cost of Tender form and an amount of Rs.9,025/- as EMD should be remitted **separately** by way of Demand Draft drawn in favour of Finance Officer, Kannur University, payable at SBI South Bazar Branch, Kannur or Kannur Branch of any other Nationalized or scheduled Bank.
3. The Tenderer shall have valid GST registration and shall furnish a copy of registration certificate along with the tender documents.
4. The successful Tenderer before signing the Agreement and within the period specified in the work order, shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit.
5. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
6. The Contractor before submitting Tender for the work shall ensure that, they have visited the Site and satisfied himself about the site conditions for the work (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen ,and materials as well as permission from Authorities for this purpose
7. Payment will be made through account and no advance payment will be sanctioned

8. Defect Liability for the work shall be 1.5 years from the date of satisfactory completion of the work.
9. Received tenders will be opened on 12.11.2026 at ...3:00 PM
10. Details of work can be had from the Planning and Development Branch on all working days up to 5 pm.

The Registrar, Kannur University, reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.

Sunil Kumar S
REGISTRAR (i/c)

To

1. Notice Board
2. Website

General Form of File PLD/E3/26884/2025 Approved by REGISTRAR (i/c) on 30-Oct-2026 09:17 PM - Page 2

General Form of File PLD/E3/26884/2025 Approved by REGISTRAR (i/c) on 30-Oct-2026 09:17 PM

KANNUR UNIVERSITY

TENDER SCHEDULE

Name of the work: -Replacement of the damaged GI Pipeline system in the main block of Mangattuparamba Campus.

ITEM NO	ITEM DESCRIPTION	QTY	UNIT	RATE		AMOUNT (Rs)
				IN FIGURES (Rs)	IN WORDS	
1.001	15.44.1 Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually / by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer- in- Charges:15 mm to 40 mm nominal bore	290	metre			
1.002	15.56 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	18.96	Sqm			
1.003	18.9.4 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching , refilling & testing of joints complete as per direction of Engineer in-Charge. External work32 mm nominal dia pipes	50	metre			
1.004	18.7.5 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer - in-Charge. Internal work - Exposed on wall 40 mm nominal dia pipes	60	metre			

General Form of File PLD/E3/26884/2025 Approved by REGISTRAR (i/c) on 30-Oct-2026 09:17 PM

1.005	18.8.2 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes& fittings, with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc.20 mm nominal dia pipes	60	metre			
1.006	18.9.5 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching , refilling & testing of joints complete as per direction of Engineer in-Charge. External work40 mm nominal dia pipes	200	metre			
1.007	13.1.1 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	18.96	Sqm			
1.008	13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	18.96	Sqm			
1.009	13.60.1 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	18.96	Sqm			
1.01	OD67211/2026-2027 Engaging labour for cleaning as per the directions of Engineer-in-charge.	4	Day			

General Form of File PLD/E3/26884/2025 Approved by REGISTRAR (i/c) on 30-Oct-2026 09:17 PM

1.011	14.72 Providing and fixing double scaffolding system (cup lock type) on the exterior side, upto seven story hight made with 40 mm dia. M.S. tube 1.5 m centre to centre,horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staricase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required location with essential safety features for the workmen etc. complete as per directions and approval of Engineer- in Charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding. Note:- This item to be used for maintenance work judicially, necessary deduction for scaffolding in the existing item to be done .	21.6	Sqm			
					TOTAL	
					18% GST	
					Grand total	
					(Rupees.....Only)	

Signature :

Name&Address of the Tenderer:

Date:

REGISTRAR (i/c)